

Fabrication, supplying of 16S.W.G CR. Sheet floor mounted type cubical pattern dust and vermin proof

Control Panel. Hinge type door knob type screw duly double coats Painting, including internal wiring providing required sizes of Copper Wire, Copper Busbar with all consumable like lug tape etc.

- | | |
|------------------------------------|-----------|
| 1. 125 Amp 4Pole MCCB | - 1No. |
| 2. 63 Amp 4Pole MCCB | - 2 No. s |
| 3. 40 Amp 4Pole MCCB | - 2 No.s |
| 4. 63 Amp 4Pole DP MCB | - 2 No.s |
| 5. Copper Strip Busbar | - 1 Set. |
| 6. C/T 150/5 | - 3 No. s |
| 7. 0-500 V Voltmeter | - 1 No. |
| 8. Amp Meter | - 1 No. |
| 9. Amper S/S | - 1 No. |
| 10. Volt S/S | - 1 No. |
| 11. Pilot indication lamp -R- Y- B | - 3 No .s |
| 12. 5 Amp potential fuse bake lite | - 3 No .s |
| 13. L.T Danger plate | - 1 No. |